

Weatherization Specifications

FY 2007 Updates

RTF Meeting

January 10, 2006

Adam Hadley

Site Built - Summary of Changes

1. Removed outdated measures and specs
2. Re-organized to coincide with the ala carte measure offering
3. Updated code references
4. Removed specs related to Utility/Contractor relationship

Site Built – Major Changes

- Window u-value from 0.35 to 0.30
- Removed outdated sections
 - Clock T-stats
 - Doors
 - Prescriptive Air Sealing
 - Window fin bar conversions.....
- Floors
 - Old: Min. R-30, or max. level to fill cavity
 - New: Min. R-30, or level to fill cavity, whichever is less